KARNATAKA PUBLIC PROCUREMENT PORTAL

Thursday, 11 August 2022 10:18:47

Welcome BASAVARAJU M(C/C)

Supported Browser Versions are: IE11, Mozilla Firefox 47,48,49,50 and 51.

Due to Security reasons, use of multi-tab/multi-instance of browser is disabled in Karnataka Public Procurement Portal.

Appealed Bids

Tender No. : BBMP/2022-23/OW/WORK_INDENT52457

Tender Title : Comprehensive Development of Roads & Drains in JP Park, Yeshawanthapura, Jalahalli and Surrounding areas in W No.16, 17 and 37 under PACKAGE- 2022-23 RRN-DIV-(15)

Department : Bruhat Bengaluru Mahanagara Palike

No Appealed Bids Available

Back

Scanned with CamScanner

Bids Received for the Tender

Tender Number: BBMP/2022-23/OW/WORK_INDENT52457

NIT Description: Comprehensive Development of Roads & Drains in JP Park, Yeshawanthapura, Jalahalli and Surrounding areas in W No.16, 17 and 37 under PACKAGE- 2022-23 RRN-DIV-(15)

Tender Evaluation Type: TWO_COVER

Tender Category: WORKS

« ‹ › »

Sl No	Supplier Name	Bid Amount(INR)	Status	View Bid Details	Actions*
1	JAVALI CHANDRANNA PRAKASH (J C PRAKASH INFRASTRUCTURES PRIVATE LIMITED)	100024272.12	RECEIVED		
2	Panduranga E ( )	97012582.56	RECEIVED		

Close

This site is best viewed in 1024x768 resolution.

Scanned with CamScanner

Financial Bid Evaluation of Goods Items

Tender Details

Tender No. : BBMP/2022-23/OW/WORK_INDENT52457

Tender Title : Comprehensive Development of Roads & Drains in JP Park, Yeshawanthapura, Jalahalli and Surrounding areas in W No.16, 17 and 37 under PACKAGE- 2022-23 RRN-DIV-(15)

Work Summary : Comprehensive Development of Roads & Drains in JP Park, Yeshawanthapura, Jalahalli and Surrounding areas in W No.16, 17 and 37 under PACKAGE- 2022-23 RRN-DIV-(15)

Bid Items

« ‹ 1 2 › »

Sl No	Item Name	Item Code	Unit	Estimate Rate	Estimate Quantity	Panduranga E ( )	JAVALI CHANDRANNA PRAKASH (J C PRAKASH INFRASTRUCTURES PRIVATE LIMITED)
1	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) Data Rate	1	Cum	212	23636.94	225.0	232.0
2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.In all kinds of soils Depth upto 1.5 m.Item No.1.4.1,	2	Cum	363.56	17634.54	386.0	398.0
3	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)	3	Cum	6327.2	162.7	6719.0	6928.0
4	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	4	Sqm	1322.2	13610.7	1404.0	1448.0
5	Providing Flush/ Ruled pointing: Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) after raking joints to depth nicely lining, including cost of materials, labour, curing as per specifications and as per directions of Engineer-in-charge.	5	Sqm	220	10787.18	234.0	241.0
6	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately).Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate.	6	Sqm	6518.6	945.78	6923.0	7138.0
7	Providing B S Slabs of selected quality roughly dressed having a size of 10cms thick and fixed in cement mortar (1:6) including fixing curing etc., complete.as directed by the Engineer in Charge of the work (Excluding GST and Area Leading Charges)	7	Sqm	837	13892.46	889.0	917.0
8	Providing one line dressing to granite stone slab / granite stone masonry as per specifications. as directed by the Engineer in Charge of the work (Excluding GST and Area Leading Charges)	8	Sqm	242	13892.46	257.0	265.0
9	Providing Machine Cutting edges to B S Slabs 2.5cms.wide as per Specifications. (Only Chamfered length Shall be recorded)inclusive of all taxes Complete.,as directed by the Engineer in Charge of the work (Excluding GST and Area Leading Charges)	9	Sqm	390	34731	414.0	427.0
10	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonary including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	10	Sqm	337.7	2169.36	359.0	370.0

Back Export to Excel

This site is best viewed in 1024x768 resolution.

Scanned with CamScanner

Tender Details

Tender No. : BBMP/2022-23/OW/WORK_INDENT52457

Work Summary : Comprehensive Development of Roads & Drains in JP Park, Yeshawanthapura, Jalahalli and Surrounding areas in W No.16, 17 and 37 under PACKAGE- 2022-23 RRN-DIV-(15)

Tender Title : Comprehensive Development of Roads & Drains in JP Park, Yeshawanthapura, Jalahalli and Surrounding areas in W No.16, 17 and 37 under PACKAGE- 2022-23 RRN-DIV-(15)

Bid Items

« ‹ 1 2 › »

Sl No	Item Name	Item Code	Unit	Estimate Rate	Estimate Quantity	Panduranga E ( )	JAVALI CHANDRANNA PRAKASH (J C PRAKASH INFRASTRUCTURES PRIVATE LIMITED)
11	Providing & laying precast drain corner cover slab of 200 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.20) Approved Data rate	11	Nos	10492	379	11143.0	11489.0
12	Providing & laying precast drain corner cover slab of 200 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(0.9 x 0.20) Approved Data rate	12	Nos	8051	800	8550.0	8816.0
13	Providing & laying precast drain slab of 230 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.23) Approved Data rate	13	Sqm	5440.98	36.95	5778.0	5958.0
14	Removing and resetting of kerb stones.	14	Nos	118	14696.76	125.0	129.0
15	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165mm respectively,400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork,curing including cost of materials,labour charges of machinery,loading and unloading,lead and lift,transportation etc., complete as directed by the Engineer in charge of the work (Excluding GST and Area Leading Charges)	15	Nos	507	19883.64	538.0	555.0
16	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces.Painting Two Coats on New Concrete Surfaces.	16	Sqm	93.5	7093.32	102.0	102.0

Back Export to Excel

This site is best viewed in 1024x768 resolution.

Scanned with CamScanner